

Tag	Equipment	MCC	Control	Voltage (V)	Output Power (kW)	Efficiency	Power Factor	Input Power (kW)	Apparent Power (kVA)	Reactive Power (kvar)	Current (A)		Plant Power Factor	
M-101	Process Pump	MCC-1	VFD	480	75	93%	0.88	80.65	91.64	43.53	110.2		0.88	
M-102	Cooling Water Pump	MCC-1	DOL	480	45	92%	0.86	48.91	56.88	29.02	68.4			
M-103	Main Conveyor	MCC-1	VFD	480	30	91%	0.85	32.97	38.78	20.43	46.7		Transformer Rating (kVA)	750
M-201	Exhaust Fan	MCC-2	VFD	480	55	92%	0.87	59.78	68.72	33.88	82.7		Plant Load (kVA)	491.1
M-202	Air Compressor	MCC-2	DOL	480	90	94%	0.90	95.74	106.38	46.37	128.0		Transformer Loading	65.5%
M-203	Secondary Conveyor	MCC-2	DOL	480	22	90%	0.84	24.44	29.10	15.79	35.0		Spare Capacity (kVA)	258.9
AUX-1	Auxiliary Facility Load	AUX	N/A	480	90	100%	0.90	90.00	100.00	43.59	120.3			
TOTAL								432.50	491.08	232.61	590.7		Transformer Full-Load Current (A)	902.1